

## (12) United States Patent Burns

(10) Patent No.:

US 6,460,040 B1

(45) Date of Patent:

\*Oct. 1, 2002

### **AUTHORING SYSTEM FOR** COMPUTED-BASED INFORMATION **DELIVERY SYSTEM**

(75) Inventor: Kevin S. Burns, Bellevue, WA (US)

(73) Assignee: Datamize LLC, Florence, MT (US)

(\*) Notice:

Subject to any disclaimer, the term of this patent is extended or adjusted under 35

U.S.C. 154(b) by 0 days.

This patent is subject to a terminal dis-

claimer.

(21) Appl. No.: 09/478,577

(22) Filed: Jan. 6, 2000

### Related U.S. Application Data

(63)Continuation of application No. 08/810,949, filed on Feb. 27, 1997, now Pat. No. 6,014,137.

Provisional application No. 60/012,341, filed on Feb. 27,

(51)	Int. Cl. <sup>7</sup>	G06F 17/30
(52)	U.S. Cl	707/10: 345/334
	Field of Search	
	707/10, 10.51; 705/26–27, 1, 14,	40; 709/218-219;
		52, 14.01; 345/747

### (56)References Cited

### U.S. PATENT DOCUMENTS

4,528,643 A		7/1985	Freeny, Jr 705/52
4,642,790 A		2/1987	Minshull et al 364/900
5,121,477 A		6/1992	Koopmans et al 395/156
5,220,675 A		6/1993	Padawer et al 395/800
5,237,157 A	*	8/1993	Kaplan 235/375
5,297,250 A		3/1994	Leroy et al 395/157

#### 4/1995 Kojima et al. ...... 358/400 5,408,333 A 5,423,041 A 6/1995 Burke et al. ...... 395/700

(List continued on next page.)

### OTHER PUBLICATIONS

Darrel Sano, "Designing Large-Scale Web Sites," John Wiley & Sons, Inc., 1996, Preface, Table of Contents, pp. 87-94, 129-137.

Darrel Sano, "Designing Large-Scale Web Sites," John Wiley & Sons, Inc., Preface, Table of Contents, pp. 87-94,


Chesnais et al., "The Fishwrap Personalized News System," IEEE, D-7803-27560X/95m, pp. 275-282, Jun. 1995.

Primary Examiner-John Breene Assistant Examiner-Mohammad Ali (74) Attorney, Agent, or Firm-Elliot B. Aronson

(57)ABSTRACT


A multimedia kiosk authoring system for use in developing and maintaining user interface screens for multimedia kiosk systems. The authoring system enables the user interface for each individual kiosk to be customized quickly and easily within wide limits of variation, yet subject to constraints adhering the resulting interface to good standards of aesthetics and user friendliness. The system may be used to provide custom interfaces expeditiously even for hundreds of kiosks presenting information from numerous independent information sources. The authoring system uses the methods of object oriented programming to define specialized object classes for instantiation on individual kiosk interface screens subject to pre-defined limitations on variability. Links are provided to an appropriate database for multimedia presentations on an interface screen of content bearing information from the information providers.


## 38 Claims, 6 Drawing Sheets




# US 6,460,040 B1 Page 2


U.S	. PATENT	DOCUMENTS		997 Scott et al 395/333
	0400-	34	5,680,619 A 10/19	997 Gudmundson et al 395/701
5,438,512 A		Mantha et al 364/419.1	5,701,500 A 12/19	997 Ikeo et al 395/779
5,446,653 A	8/1995		5,708,806 A 1/19	998 DcRose et al 395/615
5,446,837 A	8/1995		5,717,945 A 2/19	998 Tamura 395/800
5,522,024 A	5/1996	Hiraga et al 395/155	5,727,156 A 3/19	998 Herr-Hoyman
5,533,184 A	7/1996	Malcolm et al 395/161		et al 395/200.49
5,553,221 A	9/1996	Reimer et al 395/154	5,740,549 A 4/19	98 Reilly et al 705/14
5,557,798 A	9/1996	Skeen et al 705/35	5,745,360 A 4/19	98 Leone et al 364/140
5,572,643 A	11/1996	Judson 395/793	5,748,186 A 5/19	98 Raman 345/302
5,581,670 A	12/1996	Bier et al 395/326	5,748,190 A 5/19	998 Kjorsvik 345/329
5,592,605 A	1/1997	Asuma et al 395/348	5,754,938 A 5/19	998 Herz et al 725/116
5,596,695 A	1/1997	Hamada et al 395/333	5,754,939 A 5/19	98 Herz et al 455/304
5,596,702 A	1/1997	Stucka et al 395/340	5,758,351 A 5/19	998 Gibson et al 707/104
5,598,511 A	1/1997	Petrinjak et al 395/54	5,761,662 A 6/19	
5,600,771 A	2/1997	Hayashi et al 395/774	5,764,226 A * 6/19	998 Consolatti et al 345/333
5,600,778 A	2/1997	Swanson et al 395/333	5,778,398 A 7/19	
5,600,780 A	2/1997	Hiraga et al 395/334	5,787,435 A 7/19	
5,603,034 A	2/1997	Swanson 395/701	5,793,497 A 8/19	
5,608,857 A	3/1997	Ikeo et al 395/761	5,802,299 A 9/19	998 Logan et al 395/200.48
5,621,873 A	4/1997	Tanaka et al 395/779	5,802,530 A 9/1	
5,630,120 A	5/1997	Vachey 395/602	5,818,446 A 10/1	998 Bertram et al 345/334
5,630,125 A	5/1997	Zellweger 395/614	5,835,087 A 11/19	998 Herz et al 345/810
5,632,022 A	5/1997	Warren et al 395/350	5,892,938 A 4/1	999 Eastty et al 395/500
5,634,062 A	5/1997	Shimizu et al 395/762	5,920,311 A 7/1	
5,634,095 A	5/1997	Wang et al 395/326	5,959,623 A 9/1	
5,644,736 A	7/1997	Healy et al 395/341	5,959,624 A 9/1	
5,644,740 A	7/1997	Kiuchi 395/357	6,014,137 A * 1/20	
5,652,850 A	7/1997	Hollander 395/333	6,049,328 A * 4/20	
5,669,007 A	9/1997	Tateishi 395/779	6,134,547 A * 10/20	
5,671,429 A	9/1997	Tanaka 395/792		•
5,673,401 A	9/1997	Volk et al 395/327	* cited by examiner	









Oct. 1, 2002





Oct. 1, 2002



### AUTHORING SYSTEM FOR COMPUTED-BASED INFORMATION DELIVERY SYSTEM

This is a continuation of non-provisional application Ser. 5 No. 08/810,949 filed Feb. 27, 1997, now U.S. Pat. No. 6,014,137 issued Jan. 11, 2000, which is a continuation of provisional application Ser. No. 60/012,341 filed Feb. 27, 1996.

### BACKGROUND OF THE INVENTION

The present invention relates generally to electronic information delivery systems and more particularly to distributed electronic kiosk systems with multiple kiosk sites for presenting myriad amounts of information to users.

An electronic kiosk refers to a computer-based information delivery system generally accessible to some segment of the public for retrieving information or initiating transactions. An individual kiosk unit includes a display screen for presenting information to the user and some form of computer input device for the user such as a touch screen or keypad, although a full keyboard or mouse could also be provided. The type of kiosk system of interest here is an interactive system having multiple kiosk sites at which a user at an individual kiosk can select a topic or search for information about a topic from a large database of information

Such kiosk systems have become popular in recent years. They are found, for example, at museums and exhibitions, 30 airports, public transportation stations, banks, and even in retail establishments for the use of customers. Examples of kiosk systems are disclosed in U.S. Pat. No. 4,817,043 of Brown, U.S. Pat. No. 4,974,170 of Bouve et al., and U.S. Pat. No. 5,237,157 of Kaplan. Recently multimedia kiosks have appeared presenting information to the user not only as text on the display screen, but also in the form of graphics, audio clips, animated sequences of still images, and even video clips. The travel agency Thomas Cook, for example, has introduced a multimedia kiosk for arranging holiday travel, reported in *Which Computer?*, August 1994, pp.40–41.

The present invention addresses the development of an electronic kiosk system comprising a large number of individual kiosks located at a variety of different sites for 45 providing a selection of information customized to each site. For purposes of illustration the present invention is discussed in the context of a kiosk system serving a geographical region popular for skiing. Kiosks may be located, for example, at individual ski areas, at hotels and resorts in the 50 area, and at ski shops and other retail shops. The information available to a user at an individual kiosk will depend on the nature of the establishment in which the kiosk is located. A kiosk at a ski shop, for example, may provide information about the lines of rental equipment available at the shop and 55 may also provide information about the local ski areas, ski conditions, and even local restaurants and events. Kiosks at different ski shops would have to be customized for each shop at the least because rental equipment will generally provide information about the local ski areas, ski conditions and events, and may provide information about the ski shops in the area that rent and sell ski equipment. The hotel kiosk would generally not provide information about other hotels in the area and may or may not provide information on 65 restaurants outside the hotel. A ski area kiosk may provide information on lift tickets, ski conditions, specific ski runs,

ski school and day care, as well as information on ski rental, shops, restaurants, local events and the like. In a region encompassing several ski areas and towns with numerous shops, restaurants, places to stay, and places of nightly entertainment, such a kiosk system could include hundreds of kiosks, each having its own user interface and presenting its own unique selection of information.

The custom design of each individual kiosk can be a formidable undertaking. There are a great variety of possibilities for laying out the user interfaces, especially for a multimedia kiosk. A ski shop kiosk, for example, may want to display an initial stylistic presentation of the ski shop's name, perhaps overlaid on a graphic image of a skier executing an exciting ski maneuver. For a line of specialized rental skis the kiosk may present a video clip, perhaps accompanied by an audio clip, showing the ski in its specialized use. For information on a restaurant the kiosk may display a graphic image depicting patrons in the restaurant to show the atmosphere and dress appropriate to the restaurant. The kiosk may also display the restaurant menu either as a computer text file or as a graphic image of a stylish menu used in the restaurant.

These examples demonstrate the great variety of user interfaces available and highlight the effort required to develop a customized interface for each kiosk. The problem is intensified because each kiosk interface will generally have to be changed from time to time either sporadically or at regular intervals. For example, a kiosk that displays a graphic image of patrons at a restaurant to show the atmosphere and appropriate dress may find it desirable to change the graphic image with the season since a scene showing winter dress would not be appropriate in the summer. A ski shop may not carry precisely the same lines of equipment from one season to the next, and its kiosk will have to be modified to show the current equipment. Sometimes more extensive modification will be needed. A shop that carries ski equipment in the winter may specialize in other activities in the summer, for example, tennis, golf, swimming, boating or hiking. The kiosk's user interface would have to be extensively revised with the changes in season to reflect the shop's new emphasis and goods, and the information content available to the kiosk would have to be updated to include the summertime goods and activities. Ashop or hotel that displays information on ski areas in the winter may want to display information about tennis, golf and other outdoor activities in the summer. In any one geographical region changes of this sort may have to be made to hundreds of kiosks or more.

Some of the problems to be overcome to make a kiosk system of this sort commercially viable are the organization of the data for potentially hundreds of kiosks and even more data sources so that a customized selection of data will be accessible to users at each of the kiosks; the customization of the user interface for each of the potentially hundreds of kiosks or more in the system in a manner that is economically feasible; the ability to update the data available to the kiosks quickly and easily; and the ability to modify the user interface of any one kiosk quickly and easily.

the organization of data for kiosk systems and the form shop at the least because rental equipment will generally differ from shop to shop. A kiosk at a local hotel may also provide information about the local ski areas, ski conditions and events, and may provide information about the ski shops in the area that rent and sell ski equipment. The hotel kiosk would generally not provide information about other hotels in the area and may or may not provide information on the area and may or may not provide information on restaurants outside the hotel. A ski area kiosk may provide information on lift tickets, ski conditions, specific ski runs,

Hehmann, "A Networked Multimedia Retrieval Management System for Distributed Kiosk Applications," Proceedings of the IEEE International Conference on Multimedia Computing and Systems, May 15-19, 1994, pp. 342-351; P. Steiger, "MINNELLI-Experiences with an Interactive 5 Information Kiosk for Casual Users," Proceedings of the UBILAB Conference 1994 (Switzerland), Computer Science Research at UBILAB, pp. 124-133.

To assist in creating and modifying computer interface screens, a number of commercial authoring software prod- 10 ucts are available. With such software a programmer can design the layout of a display screen such as the size, character and placement of buttons and windows on the screen and combine text, graphics, audio and video into a user-friendly application screen interface. In general, author- 15 ing tools comprise prewritten computer code having a functionality for reading a data structure that defines a task to be taken and performs the task based on the data. Examples include Macromedia Director, Asymmetrix Multimedia ToolBook, and Oracle's Media Objects. High-end 20 authoring systems have the capability to integrate different media and they include full application-building programmability similar to that found in database packages. Most authoring tools define a screen and the specific attributes of the screen such as the definition of a video window that will 25 play a specified video clip or show a text file or a graphic

### SUMMARY OF THE INVENTION

The present invention provides a multimedia kiosk 30 authoring system for use in developing and maintaining multimedia kiosk systems. The authoring system enables the user interface for each individual kiosk to be customized quickly and easily within wide limits of variation, yet subject to constraints adhering the resulting interface to 35 good standards of aesthetics and user friendliness. The system may be used to provide custom interfaces expeditiously even for hundreds of kiosks. The authoring system also provides for organization of information from numerous information sources, referred to herein generally as 40 information providers. The system makes it easy to set up, maintain, and update a great variety of kiosks with large amounts of information potentially available to each kiosk. Each kiosk, however, is customized to present only the information that is appropriate to that kiosk. When a new 45 information provider subscribes to the system, it may easily be incorporated into the system so that it is available for all kiosks. All individual kiosks may have available to them the entirety of the latest information. The present authoring the field at potentially hundreds of kiosk sites.

The present authoring system is particularly advantageous in that it may be used by persons with little or no experience in the intricate details of computer programming thereby making it easier for a larger number of persons to set up 55 kiosk interface screens. It is a further advantage of the present authoring system that an individual using the authoring software to devise a kiosk interface screen (that individual is referred to herein as a "system author") is only given a limited range of choices for stylistic and functional 60 elements appearing in the screen displays. In this way major aesthetic or functional design choices such as button styles and sizes, window borders, color combinations, and type fonts as well as hierarchical methods of retrieving information may be built into the system taking into account the 65 considered opinions of aesthetic design specialists, database specialists, and academic studies on public access kiosk

systems and user preferences and problems. Only a limited range of pre-defined design choices is then made available to a system author. Nevertheless, the authoring software is structured to make it amenable to change for example to permit new elements to be added to the system or to take into account the results of new studies on user interactions with computer kiosks.

Other aspects, advantages, and novel features of the present authoring system are described below or will be readily apparent to those skilled in the art from the following specifications and drawings of illustrative embodiments.

### BRIEF DESCRIPTION OF THE DRAWINGS

FIG. 1 is a diagrammatic representation of a distributed kiosk system for implementing the present invention.

FIGS. 2A and 2B are examples of kiosk screen display

FIG. 3 is an example of a screen layout joined table for implementing a kiosk authoring system of the present inven-

FIG. 4 is an example of a Region/Resort database joined table.

FIG. 5 is an example of a Shop/Manufacturer database joined table.

### DETAILED DESCRIPTION OF ILLUSTRATIVE **EMBODIMENTS**

For purposes of illustration an embodiment of the present invention is described in a distributed kiosk system serving a geographical region popular for skiing. FIG. 1 shows three representative kiosks 10 located in a ski shop (the "ABC Ski Shop"), a ski area (the "Big Mountain Ski Area"), and a hotel (the "ZZZ Hotel"), all located in a geographical region indicated generally at 11. FIG. 1 shows a representative geographical region situated in the ski country of Northern California. The system is not limited to small numbers of kiosks, but may include hundreds or thousands of kiosks serving a number of localized geographical regions. Indeed, many of the features of the invention are especially advantageous in such large and widely distributed systems. The system may also include remote and isolated kiosks such as kiosk 12 located in a travel bureau removed from ski country 11. The embodiment of FIG. 1 includes a master computer 13 at yet another location that may be used for software implementation of new subscriber kiosks on the system and maintenance of old kiosks.

Kiosks commonly take the form of dedicated stand-alone system avoids the need to keep track of different versions in 50 stations having a display screen that may be a touch screen and/or may be used with a keypad. In some settings, however, a self-contained stand-alone kiosk would be out of place and the function of the kiosk may be served equally well by a desktop computer with a touch pad or mouse or even a keyboard. For example, kiosk 12 of FIG. 1 in a remote travel bureau may take the form of a desktop computer in the travel bureau office. "Kiosk" is used herein in this broad sense to include stand-alone kiosks as well as general purpose computers configured to serve the same functions as a stand-alone kiosk. As configured in the present system each kiosk also includes its own data storage capability such as a high volume hard disk drive, although the system could operate from a central database server such as master computer 13 in FIG. 1 when suitable bandwidth for communications with the many kiosks is available. As will be described below, if the system is not implemented with a central database server, it is advantageous for each

kiosk to store the entire database of information for all kiosks in the system even though each kiosk will not generally use the entire database.

Hardware implementations of a kiosk as a stand-alone unit with a touch screen or keypad are well known and need not be described in detail here. Of more significance to the present invention is the method by which the software for the kiosk units is configured.

Before the software is described in any detail, it is instructive to look at examples of kiosk screen layouts 10 designed by the authoring system of the present invention. FIG. 2A shows a representative layout of a display screen 20 from the ABC Ski Area kiosk 10 that is rich in structural details. One column and one row of buttons 21 of a first type are disposed along two edges of the screen. Each button 21 15 has a textual portion 22 with text identifying a category of information and a graphics portion 23 showing a graphical image appropriate to the associated information category. The bulk of the screen is occupied by a main window 24 that has a variable display. When the kiosk is not in use, window 20 24 may display a primary scene from the ski area with overlaid text identifying the area and perhaps giving instructions for use. When a user activates a button 21, main window 24 displays information about the topic associated with the button. In FIG. 2A the user has activated the 25 restaurant button in the upper left corner of the screen. Main window 24 displays a background graphical image of an attractive scene from the ski area overlaid with three columns of buttons 26 of a second type with textual labels 27 identifying restaurants and other eating establishments 30 available at the ski area. Also overlaid on the background image in main window 24 are textual labels 28 identifying the general locations of the eating establishments. At the bottom of the screen are additional screen maneuvering buttons 29. For purposes of illustration in FIG. 2A the 35 graphical images on buttons 21 and in main window 24 are shown only in diagrammatic format. The authoring software can insert a variety of image types at the selection of the system author such as photographs, artwork or even video clips.

A closer look at the structure of the screen layout of FIG. 2A is in order. The buttons 21 have a fixed predefined size, which is chosen not only to make them aesthetically pleasing in appearance, but also easy to use on a touch screen by persons generally unpracticed with touch screen operation. 45 The button placement in FIG. 2A is generally fixed along two adjacent edges. This is an aesthetic choice, but it is a choice that is forced by the authoring software to assure that once an aesthetically and functionally acceptable button size and layout has been chosen, it will be maintained throughout 50 all further screen layouts for all kiosks without having to expend time and effort re-creating an acceptable button layout anew for each kiosk. Other aesthetic button layouts may also be used, but once a general button layout is devised. The software makes it available for use in all kiosk 55 interface screens. Considering that many many screen layouts will generally have to be set up and then regularly revised, limiting the system author's freedom to devise new button patterns and button styles greatly enhances the ease with which new kiosks may be brought in operation and 60 ensures that the button pattern will be aesthetically and operationally acceptable.

The screen layout of FIG. 2A shows twelve buttons 21 of the first type. If a kiosk screen calls for fewer buttons, then the spacing between the buttons is automatically adjusted, 65 but the button size and row and column placement are unaltered. If the screen calls for more buttons, then one

button on the initial screen is a "MORE" button activating display of additional buttons, which will then include a "BACK" button for return to the previous display of buttons. This is an example of a control built into the authoring software to ensure that the buttons cannot be made too small so as to impair their readability or ease of use.

Notwithstanding the frequent advantages of the fixed geometric button placement as in FIG. 2A, an alternative free button placement is also provided as illustrated in the screen layout of FIG. 2B. This is particularly beneficial when only a few buttons 21 are to be displayed. FIG. 2B shows an alternative screen layout with a main window 24a and three buttons 21a of the first type positioned at coordinates and in orientations specified by the system author. The buttons 21a activate associated displays in main window 24a.

Having described the appearance and basic functionality of example kiosk interface screens, a more detailed description is now given of an implementation of the authoring system according to the invention. A given screen will include a variety of elements for presentation to a user such as one or more windows, one or more background images or artwork for providing a backdrop for a window or for background within a window, a number of buttons, a number of "hot spots," i.e., areas on the screen for activating actions, text strings, video clips, audio clips, slide sequences, or animation sequences. These elements are grouped into element types. For example, there may be several styles of buttons, each style constituting a button type, or there may be several styles of windows, each constituting a window type. Thus, the element types may include one or more button types, window types, text types, video types, and so on. Buttons and hot spots are sometimes referred to herein collectively as activation sites, and button types and hot spot types are sometimes grouped together herein as examples of activation types.

The authoring system uses the methods of object oriented programming. The system is specified by the following Object Class Definition Tables. The entries in these tables follow customary object oriented programming nomenclature and will be readily understood to those skilled in the art of object oriented programming. The particular implementation described here was developed for the Microsoft Windows® platform using the Microsoft Software Developers Kit (SDK) and that nomenclature is followed here. The classes used here are derived from or supplement classes provided by Microsoft SDK.

	CLASS DEFINITION TABLES Project Class		
Attibute Type	Attribute Name	Description	
long	IProjectID .	Project ID	
CString	sProjectName	Project Name	
long	IHomeScreenID	ID of the Home Screen for the Project-not	
CString	sHomeName	known initially Name of the Home Screen	
Туре	Name	Description	
	Screen (	Class	
long	IScmID	Screen ID	
CString	sScrnTitle	Screen Title	

		tinued			-contin	iucu
CString	sScrnBkgnd	Screen Background - File		LOGFONT	lflext	Provide a LOGFONT if te
Name		J			ii ica	
long	1ScmColor 1	Screen Color		;		is not th displayed as
long	[ProjectID]	Project ID				it is stored in the RTF
long	[Parent	Parents ID		2001		File.
				BOOL	bBorder	Display Window Border
long[]	[Children[]	Array of Children ID's		DWORD	dwStyle	Window Styles
int	nTransition	Transition effect for screen		DWORD	dwBorder	Border Style
		to screen		BOOL		
CString	sVoiceOver	Voice Over file name	10		bTransparent	Display the Text
			11	J		Transparently with no
		associated with				Frame, etc. on the
		screen				parent window
CString	sHelpFile	Help File name associated			Text Objec	
	Contr	with the screen			<del></del>	<u></u>
	_ count	or Class		CString	sText	Text to display
long	[ScreenID]	Screen ID:	1:	5 CPoint	ptText	Upper Lt Coordinate of
.06	tociccing	Screen ID; every control is				Starting Location to
		associated with a				Display Text
		screen		double	dRadian	
long	ICtrlID	Control ID; every control		DWORD		Angle if any to display Tex
-				DWOKD	dwEffect	Effect to use to Display
long	[ForeColor	has a unique ID				Text
rong	TroteColor	Foreground Color;	20	LOGFONT	IfText	LOGFONT structure to be
		foreground color of	20	,		used to display the
		the control				
long	IBackColor	Background Color,				Text
-					Audio Objec	t Class
		background color of				<del></del>
la	*** 1	the control		CString	sWavFile	Name of the WAV File to
long	ILink	Link; ID of screen to which		-		play. A way file is
		control is linked	25			
WORD	wTransition	Transition; #define				assumed but other
						audio file formats like
		describing screen				MPEG, AVI, are
		transition effect				supported. The file
POINT	ptControlLt	Upper left hand corner of				
		control				type is based on the
POINT	ptControlRt	Lower left hand corner of	20	WORD		file extension.
	Production		30	WORD	wDelay	Delay as to when to start
Wann		control				the Audio
WORD	wHeight	Control Height		BOOL	bRepeat	
WORD	wWidth	Control Width			orrepent.	Set to true to replay the
double	dRotate	Angle of control in radians				Audio clip when
BOOL	bAuthor					complete
2002	ortunioi	Author Mode (T) Authoring		BOOL	bVolControl	Set to true to allow user to
DO01		(F) playback engine	35			alter Audio & even
BOOL	bAction	Action; specifies if a				mute Audio.
		control has an action			Video Ohioa	
		(T) or a Link (F)			Video Object	Class
long	LAction	Action ID; a #define		001		
Ū				CString	sVideo	Name of the video file to
	ъ	describing the Action				play. Again, the
	Button	Class	40			Video type is
			40			determined by the
WORD	wButtonType	Type of button				
WORD	wFrameStyle	Frame Style		CRect	-D	files extension.
long	IFrameColor			CRea	cRectWin	Rectangle of where to
WORD	wFrameSize	Color of the frame				place the Video Window.
		Frame size in pixels		BOOL	bRepeat	Set True to Repeat the
CString	s'l'itle	Title of button			•	
WORD	wLocation	Location of title on button	45	BOOL	bAudio	Video when complete
long	lTitleColor	Color of the Button Title				Set True to play Audio
	sFont	Font Name		UINT	uiEffects	Effect to play between
						Clips
CString	hBald					Set to true if there are
CString BOOL	bBold	Font Attrib - Bold		BOOL	bMultiple	
CString BOOL BOOL	bltalic			BOOL	bMultiple	multiple cline to -1-
CString BOOL BOOL		Font Attrib - Bold Font Attrib - Italic		BOOL	bMultiple	multiple clips to play
CString BOOL BOOL WORD	bltalic wPtSize	Font Attrib - Bold Font Attrib - Italic Font point size	50	BOOL	bMultiple	multiple clips to play specified in CString.
CString BOOL BOOL WORD	bitalic wPtSize IDropColor	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color	50	BOOL	bMultiple	multiple clips to play specified in CString. If there area multiple
CString BOOL BOOL WORD long WORD	bitalic wPtSize IDropColor wDropSize	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size	50	BOOL	bMultiple	multiple clips to play specified in CString. If there area multiple
CString BOOL BOOL WORD	bitalic wPtSize IDropColor	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one	50	BOOL	bMultiple	multiple clips to play specified in CString. If there area multiple clip then CString is a
CString BOOL BOOL WORD long WORD CString	bitalic wPtSize IDropColor wDropSize sFile	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop Shadow size File Name for image (if one used)	50		·	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names.
CString BOOL BOOL WORD long WORD	bitalic wPtSize IDropColor wDropSize	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop Shadow size File Name for image (if one used)	50	BOOL	bMultiple bBorder	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a
CString BOOL BOOL WORD long WORD CString	bitalic wPtSize IDropColor wDropSize sFile	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of	50	BOOL	bBorder	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border
CString BOOL BOOL WORD long WORD CString CPoint	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of Image			·	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border Style of Border to use on
CString BOOL BOOL WORD long WORD CString CPoint	bitalic wPtSize IDropColor wDropSize sFile	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of Image Lower right hand corner of	50	BOOL DWORD	bBorder	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border
CString BOOL BOOL WORD Jong WORD CString CPoint	bitalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image		BOOL	bBorder dwBorderStyles	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border Style of Border to use on the Video Window
CString BOOL BOOL WORD long WORD CString CPoint Cpoint WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image		BOOL DWORD	bBorder	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should
CString BOOL BOOL WORD long WORD CString CPoint Cpoint WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image		BOOL DWORD	bBorder dwBorderStyles	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open
CString BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of Image Lower right hand corner of image Width of image Height of image		BOOL DWORD BOOL	bBorder dwBorderStyles bOpen	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability.
CString BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State		BOOL DWORD	bBorder dwBorderStyles	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to True if MCI control
CString BOOL BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD ONG WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset		BOOL DWORD BOOL	bBorder dwBorderStyles bOpen	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to True if MCI control
CString BOOL BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD ONG WORD	bitalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset inghandle	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image	55	BOOL DWORD BOOL	bBorder dwBorderStyles bOpen	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to True if MCI control functionality is provided,
CString BOOL BOOL WORD long WORD CString CPoint Cpoint WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image		BOOL DWORD BOOL	bBorder dwBorderStyles bOpen	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar,
CString BOOL BOOL WORD ong WORD CString CPoint VORD WORD ONG WORD CPOINT ONG WORD ONG WORD ONG WORD ONG	bitalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset inghandle	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand comer of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image	55	BOOL DWORD BOOL	bBorder dwBorderStyles bOpen bControl	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop.
CSTring BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD WORD WORD NORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset imghandle Text Windo	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image	55	BOOL DWORD BOOL	bBorder dwBorderStyles bOpen	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop.
CSTring BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD WORD WORD NORD	bitalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset inghandle	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image ow Class Handle to a	55	BOOL  BOOL  BOOL	bBorder dwBorderStyles bOpen bControl  Animation Object	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop.
CString BOOL BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD WORD WORD WORD at the string WORD the string WORD WORD WORD WORD WORD WORD WORD WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset intghandle Text Windo	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image ow Class  Handle to a CRichEditTextControl	55	BOOL DWORD BOOL	bBorder dwBorderStyles bOpen bControl	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop. ct Class
CSTring BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD WORD WORD THE CONTROL TO TH	bltalic wPtSize IDropColor wDropSize sFile  ptPictLeft  ptPictRight  wWidth wHeight wState nYOffset imphandle  Text Windo hWndTextWin  cRectWin	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image ow Class Handle to a	55	BOOL  BOOL  BOOL	bBorder dwBorderStyles bOpen bControl  Animation Object	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop. ct Class
CString BOOL BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD ONG WORD	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset intghandle Text Windo	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image ow Class  Handle to a CRichEditTextControl Coordinates of the Window	55	BOOL  BOOL  BOOL	bBorder dwBorderStyles bOpen bControl  Animation Object	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop. ct Class  Name of the animation file to play. Again, the
CString BOOL BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD WORD WORD WORD WORD The control of the control CENTRE CENTRING CSTRING CSTRI	bltalic wPtSize IDropColor wDropSize sFile ptPictLeft ptPictRight wWidth wHeight wState nYOffset imghandle Text Winde hWndTextWin cRectWin sTxtFile	Font Attrib - Bold Font Attrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image Ow Class  Handle to a CRichEditTextControl Coordinates of the Window Name of the RTF to display	55 60	BOOL  BOOL  BOOL	bBorder dwBorderStyles bOpen bControl  Animation Object	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names. Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop. ct Class  Name of the animation file to play. Again, the Animation type is
CSTring BOOL BOOL WORD ong WORD CString CPoint Cpoint WORD WORD WORD WORD WORD THE CONTROL TO TH	bltalic wPtSize IDropColor wDropSize sFile  ptPictLeft  ptPictRight  wWidth wHeight wState nYOffset imphandle  Text Windo hWndTextWin  cRectWin	Font Altrib - Bold Font Altrib - Italic Font point size Drop Shadow Color Drop shadow size File Name for image (if one used) Upper left hand corner of Image Lower right hand corner of image Width of image Height of image Button State Image Y Offset Handle to the image ow Class  Handle to a CRichEditTextControl Coordinates of the Window	55	BOOL  BOOL  BOOL	bBorder dwBorderStyles bOpen bControl  Animation Object	multiple clips to play specified in CString. If there area multiple clip then CString is a file with a list of clip names Set to True if there is a Border Style of Border to use on the Video Window Set to True if we should provide File Open Capability. Set to Ture if MCI control functionality is provided, such as a slide bar, repeat, stop. ct Class  Name of the animation file to play. Again, the

	-continued			
CPath	cPathAnim	Path of the Animation		
ROOL	bRepeat	Set True to Repeat the		
		Video when complete		
BOOL	bAudio	Set True to play Audio		
BOOL	bMultiple	Set to true if there are		
		multiple clips to play		
		specified in CString.		
		If there are multiple		
		clip then CString is a		
		file with a list of clip		
DWODD		names.		
DWORD	dwBorderStyles	Style of Border to use on		
	Image Obj	the Animation Window lect Class		
CString	clmane	None of the form of the co		
Couring	slmage	Name of the Image file to		
		display. Again, the image type is		
		determined by the file		
		extension.		
BOOL	bBorder	CATCHISION		
DWORD	dwStyle	Image Style Attributes, like		
	•	border size, border		
		color, Drop Shadow,		
		Transparency		
CPoint	ptUpperLt	Upper Left Corner of the		
		Image		
UINT	uiWidth	Width of the Image		
UINT	uiHeight	Height of the Image		
double	dAngle	Angle to display the Image		
CRECT[]	rectHot	Army of Rect Hotspots in		
		the Image		
	_Slide Obje	ect Class		
CString	sFiles	A File containing the		
		images to display in		
		the slide window.		
BOOL	bDistort	Set to true if Images can		
		be distorted when		
		displayed		
BOOL	bBorder	Set to True if the Object		
		has a border		
DWORD	dwStyles	Sets the Objects Styles,		
		such as border size,		
		border color, Forward		
		and Backward		
UINT	uiDelay	Buttons provided		
CPoint	ptUpperLi	Delay between slides Upper Left Corner of the		
	lundiluna.	Image		
UINT	uiWidth	Width of the Image		
UINT	ui <b>Height</b>	Height of the Image		
double	dAngle	Angle to display the Image		
Nav Object Class				
CString	sFile	Name of the Nav File		
CRect	cRectWin	Rectangle of location for		
		control		
BOOL	bBorder	Set to True to display a		
		border.		
DWORD	dwStyles	Styles for the Control, like		
		border size, border		
CDaniti	-D	color		
CRect[∏]	cRectNav	Army of Hotspots for the		
		Nav, Store X and Y		
		for Hotspots. The frames will be		
		determined on the fly.		
		The lay		

The project class defines the types of pre-established projects that are available to be implemented on a kiosk system. "Project" here refers to a kiosk system implementation devoted to a specific theme; for example, the kiosk system based on a skiing theme illustrated here is an example of a ski implementation and constitutes one project. Other projects could be for example a golf project or a 65 mountain biking project. In short, "project" refers to a grouping of a series of screens with a common theme. A

project is associated with a home screen with which a full set of screens for the project is linked.

The screen class is associated with all the controls for a given screen. All the classes are derived from the control class, which defines the common attributes that all classes may share. The attribute "bAuthor" in the Control Class Definition Table defines two modes of operation. In the author mode a system author can manipulate the various elements to be placed on a screen, such as placing buttons 10 or editing attributes within the permissible attribute ranges. In the playback mode the system author can play back the current configuration of a screen as it will be presented to a user. Note in the Control Class Definition Table that since the defining points for controls do not have to be rectangular, points may be used to support non-rectangular objects. The button class is derived from the control class. For the text window class the control is derived from a CRichEditTextControl class, which is a class provided with the Microsoft Windows SDK. This class handles predetermined logic for handling rich text format (RTF) text such as word wrapping 20 or font selection. In this table "LOGFONT" refers to a structure provided by Windows SDK for defining a font and its attributes. The attribute "bTransparent" enables the system author to display text in a window without displaying the window itself. That is, the window is transparent, the text 25 is not. This provides an alternative means of formatting text other than using a text object. Using a transparent window makes it easier to format large amounts of text to control word wrap, highlighting and the like. The use of RTF format can be convenient for example to display text with prede-30 termined characteristics. For example, it may be desirable to display a ski report with a standardized font with keywords (e.g. Excellent Conditions, Poor Conditions, Warning) highlighted or offset in different colors. Through this class the format for presentation may be pre-established for the 35 system author. In the Text Object Class Definition Table the attribute "dwEffect" refers to the choice of dynamic transitioning effect (fading and the like) to be used, if any, when the text is first displayed on (or removed from) the screen. The audio object class is used for presenting audio clips to 40 the user. The table entry "wDelay" refers to the delay before an audio clip begins to play after a kiosk user activates it. In the Video Object Class Definition Table the entry "uiEffects" refers to a dynamic transitioning effect to activate between video clips when more than one video clip is to be played 45 sequentially or one video clip is to be repeated. The entry "bOpen" refers to the ability of a kiosk user to open a video clip by activating an activation site on a screen. The entry "bControl" puts up a media control interface including buttons and slide bar for a kiosk user to start, stop, and 50 fast-forward and back within a video clip. In the Animation Object Class Definition Table the entry "cPathAnim" defines a stored array of points defining a locus for an animation sequence to follow across in display screen as the sequence progresses. For example, an animation sequence could move 55 along an elliptical path as the clip is played. The image object class defines image objects to be used as stills for backgrounds or for foregrounds, for example, a product image such as a ski boot and images to be used as part of a sequence for slide presentations. The nav object class refers to navigable objects. For example, a kiosk user may be permitted to navigate an image of a product such as a ski boot. The boot is stored as a series of still images from different angles collected together in an array. A kiosk user may activate controls to look at the front, side or back of the ski boot.

The authoring software includes the capability of including hot spots in a navigable object so that the user may

12

obtain further information or activate further screens. For example, a buckle on the ski boot may constitute a hot spot that the user can activate to get more detailed views of the buckle or to activate a video clip of the operation of the buckle. To make it easier and quicker for a system author to 5 define such hot spots, the authoring system proceeds as follows. A region to be designated a hot spot is defined on only one image, referred to herein as "hot spot defining" image. If a further hot spot to be defined is not visible in the first hot-spot-defining image, then a second image will also 10 be designated a hot spot defining image. The hot spot locations on the hot spot defining image or images are stored in a lookup table. When the user rotates a view (that is to say, progresses to a further image in the navigable sequence) and attempts to activate a region on the rotated view, the 15 software operates to back track to the hot spot defining image from which the current image unfolded and looks up the coordinates for any hot spots defined in that image. The appropriate action is then taken. This procedure represents a considerable savings for the system author in a kiosk system 20 having hundreds of kiosks and many navigable objects. It is not necessary for the system author to define separate hot spots on each image in an array making up a navigable object.

The interrelations amongst the object classes in a system 25 implementation is shown the joined tables of FIG. 3. This series of tables describes the relationship of a project, the screens, and the screen objects. The screen layout tables also define screen types and the locations at which objects appear on screens of given type. For example, a screen of type 1 will have its own associated screen definitions with one object to a pre-defined limiting number N of objects. A screen of type 1 may then be defined having from one to N objects and the objects will always be placed appropriately. Some example tables will now be discussed.

35 Project Table

The project table contains a unique project ID, the project name, the home screen ID and the Home Screen Name. All screens in the system are necessarily linked to a specific project. Example:

Project ID: 004989788 Project Name: Ski

Home Screen ID: 004000001 Home Screen Name: HomeScreen

The project ID is used to link the project to the screens comprising the project.

Screen Table

The screen table contains a unique ID for a screen in a project. The screen is linked to a project by the Project ID. The Screen Table contains a Project ID, Screen ID, Screen Name, Screen Type ID and other screen attributes. The Screen ID is used to link a screen to objects on the screen; the Project Id is used to link a Screen to a Project; and the Screen Type ID is used to link a screen to a screen type. Each screen will have a screen type. A screen type is a template that describes the permissible layout for a screen. If a screen has a Screen Type ID, the screen is linked to a Screen Layout which will define the screen look. Example:

Project ID: 004989788 Screen ID: 004000001 Screen Name: HomeScreen Screen Type ID: 0000500061

This screen is part of the Project Specified by the Project ID and has a screen type that includes "Lower Buttons" in 65 this example. While that is not expressly given in the screen table, it is apparent by reference to the screen type designated the screen type

nated by Screen Type ID 0000500061. The objects associated with this screen are then read from the screen type and are placed on the screen as described by the Lower Button Screen Template.

Object Table

The Object Table contains a Screen Id, which identifies the screen the object is associated with, a Control ID, which defines the type of object and the attributes associated with the object. Example:

Screen ID: 004000001

Control ID: 0000000001

Control Type: Video Window

This Video Window object is associated with the Screen identified by the Screen ID and has the attributes that are defined in the Object table. The control is linked to the object table via the Control ID.

Object Info Table

The Object Info Table contains a Control ID and other control attribute information. It is associated with an object via its Control ID. Example:

Control ID: 0000000001 Control Type: Video Window Control Name: HomeScreen Video

The Object Info Table provides the attributes associated with an object. In turn the object is associated with a screen via the Screen ID.

Screen Type Table

The Screen Type Table defines a screen type and the project with which this screen type is associated. The Project ID is a unique ID specifying the project to which this Type of screen is attached. The Screen Type ID specifies a specific screen type template. Example:

Project ID: 004989788

Screen Type: Lower Button

Screen Type ID: 0000500061

The Screen Type is a predefined screen layout that can be used to dynamically build an interface.

Screen Layouts Table

The Screen Layouts Table defines the possible layouts for a screen type. It will contain several options for the look of the screen under different circumstances. The Screen Type ID links the screen layouts to a screen type. Example:

Screen Type ID: 0000500061 Screen Type: Lower Button

1 Object Coordinates: Rect

The Screen Layout table defines the different appearances available for a screen. The Screen Type Lower Button has a layout that contains the layout for one Button Object, two Buttons Objects, etc. The system author can then determine how many object are to be placed on a screen and what the screen type is and pick the appropriate coordinates and place the objects on the screen in a predetermined functional and aesthetic format.

By way of summary, a kiosk user interface authored using the present system includes of the following components: a project component, a screen component, and a screen object component including buttons, hot spots, video, audio, text, windows for video, audio, text, animation. The project component stores data about the program along with a link to a list of screens in the program as well as the project name and ID. The screen component stores information about a specific screen. A screen can contain a background image or solid color, text, a textual reference to the screen, a screen ID, and the IDs of the parent screen and any child screens. This arrangement in effect forms a doubly linked list that

allows the system to be displayed in a hierarchy as well as to be navigated in a linear fashion when desirable.

The screen component contains a screen object definition file that defines the objects to be placed on the screen. The procedure is as follows. The first field in the data structure 5 is the Boolean field bMath. If bMath is TRUE, then the object locations are ignored and the objects are placed according to a mathematical formula. This is carried out as follows. First get the kiosk ID from the definition file. Each subscribing client has an ID, and each of the client's kiosks 10 has an ID. Using the unique kiosk ID perform a lookup for data pertinent to the screen. For example, if the kiosk is at the ABC Ski Shop and the screen is for X Company ski boots, perform a lookup to see what X Company boots the ABC Ski Shop carries. Each time an X Company ski boot carried by the ABC Ski Shop is found, a counter is incremented. Once the lookup has traversed the system, the counter will give the total count of X Company boots at the ABC Ski Shop. Based on this count, a calculation is then 20 made to determine where the total count of objects should be placed on the screen. For example, determine the width and height of the screen and divide each by the total count of objects to determine the space to be allocated to each object. Then calculate (or lookup) the screen coordinates positioning each object along the lower edge of the screen or, if there are more than, say, seven objects, the lower edge and the left edge of the screen.

If bMath is FALSE, then the objects are to be placed in predefined locations. The database is traversed as before to determine how many objects are to be placed on the screen. However, now a screen definition table defines where the objects equal in number to the total count are to be placed. In this mode the object locations are predefined.

Once the object locations are determined, the entries in a database specify the text and/or pictures associated with the objects. The object may then be labeled and drawn. Pseudocode describing this interface is given in Table I.

### TABLE I

```
<Entering new screen - get screen ID passed in as a parameter>
Based on Screen ID, look up the screen's object definition file
     perform lookup on screen ID to get Lookup Value
            <e.g., X Company ski boots
     Once the lookup key is obtained
            Read the system ID
            Perform a database lookup based on system ID and lookup
                key <e.g., ABC Ski Shop AND X Company ski boots>
            Traverse the system ID looking for lookup keys
                Count the matching items
     Once all objects to be placed on the screen have been obtained
            Calculate the object locations
Get screen width
                Get screen height
                based on screen width determine x coordinate of first
                      item
                      Screen Width - 1024
                      There are six objects
                      1024/5 = 205
                      Ideal sizing = 167
                      Calculate proper spacing across screen using
                           objectWidth = 167
     Once all object locations are defined
            Perform lookup in the database using system ID and lookup
                With match get "Object Text"
                               get "Picture"
                                get "Video"
                               get "Action"
     Once the object characteristics are obtained
            Label and draw the object
```

### TABLE 1-continued

Perform lookup on screen ID to get Lookup Value <e.g., X Company ski boots> Once the lookup key is obtained Read the system ID Perform a database lookup based on system ID and lookup key <e.g., ABC Ski Shop AND X Company ski boots> Traverse the system ID looking for lookup keys Count the matching items Once all objects to be placed on the screen have been obtained Perform a lookup to get the predefined object locations epredefined object locations will depend on the number of items> Once all the object locations are defined Perform lookup in the database using system ID and lookup With match get "Object Text" get "Picture" get "Video" get "Action" Once the object characteristics are obtained Label and draw the object

To implement the kiosk system, a database of all information to be displayed at any individual kiosk is constructed. The database is formed using standard database methods and software. In the illustrated embodiment Btrieve database software was used to create and maintain the database. The method of the invention is implemented so that other commercial database software products could readily be substituted for Btrieve. The authoring system of the present invention then allows each kiosk to be customized quickly and easily while maintaining a high degree of variability in the screen layouts without sacrificing aesthetic appearance. Unlike authoring systems of the prior art, which generally create a specific version of the software for each kiosk, the present authoring system uses the same software at each kiosk, but merely redefines definition tables to configure an individual kiosk. The definition tables can be redefined at the kiosk site or remotely from master computer 13. In this way for example when a ski shop stops providing 40 one ski line and substitutes a competitor's ski line, it is only necessary to change a definition table to update the kiosk interface. No change in the software is called for.

A description is now given of the organization of the database of information available to be displayed on a kiosk screen in the example of FIG. 2A. FIG. 4 shows an example of a joined table structure that is used to describe the category of resorts. The joined table is a series of related tables describing the resorts and their offerings. By using the information in these tables in conjunction with the informa-50 tion in Screen Layout tables discussed above, a system author can create a user interface on the fly, i.e, in real time, instead of having to pre-define each screen specific to each kiosk. For example, to prepare the user interface for a kiosk in the California Region, one performs a lookup in these 55 tables using the database software to determine the resorts in the database for California. This gives a count of the number of resorts in the California region, which may then be laid out on the screen. Performing lookups through the joined table structure provides information for developing the 60 further hierarchical screen layout including information for each resort, ski runs, rental shops, restaurants and the like.

We turn now to a description of the individual tables making up the joined table of FIG. 4. The Region Table

The region Table provides a unique Region ID as well as a Region Name. The Region ID is a unique long integer. Any scheme may be used for defining IDs occurring in this and

15

all the other tables of the database. The Region Name provides a descriptor for the Region. Example:

Region ID: 000909100 Region Name: California Region ID: 000800101

Region Name: Pacific North West

All resorts are associated with a region. One performs a lookup of the number of Regions in the system to determine how many buttons should appear on the Region Screen. To 10 place the buttons on the screen, either a screen layout associated with a predefined screen type may be used or a mathematical formula may be used to position a standard button along the bottom or side of the screen as in FIG. 2A. Resort Table

The Resort Table provides a Unique Resort ID, a Resort Name, a Region ID, and other information about the resort such as the number of chair lifts, the number of Runs, whether the resort has other Facilities or Activities. The Resort ID is a unique identifier for a specific resort, and the 20 Region ID defines an association provided through a join to a Region. As implemented here, all resorts are found within one Region. The rest of the information in this table gives general information about the resort. Example:

Resort ID: 000909190

Resort Name: Big Mountain Ski Area

Region ID: 00909100 Number of Runs: 110 Number of Chairs: 34

Facilities True Activities True

This information is used to determine the screen layout. If a Region has four resorts linked to it, then the screen will have four corresponding button objects. As indicated above, 35 the button objects can be placed on the screen either by mathematical formula giving screen coordinates or by screen type. If the Resorts screen has a screen type associated with it, then the screen layout will be looked up based on the number of Resorts associated with a Region. Chair Lift Table

The Chair Lift Table provides a Unique Resort ID, a Chair ID and a Chair Name. The Resort ID links the Chair Lift to a specific resort and the Chair ID links the Chair to a record in the Chair Lift Info table. The Chair lift Name provides the 45 Activity to an Activity Record. Example: common name of the lift. Example:

Resort ID: 000909190 Chair ID: 000000001 Chair Name: Siberia Chair Lift Info Table

The Chair Lift Info Table provides a Unique Chair ID, a Chair Name and other information about the chair such as vertical rise and terrain served. Example:

Chair ID: 000000001 Chair Name: Siberia Lift Type: Express Quad Hourly Capacity: 2600 Skier/hour

Vertical: 1600' Length: 5000'

Terrain Served: Intermediate/Advanced

Run Table

The Run Table provides a Chair ID and a Unique Run ID as well as the Ski Run name. The Chair ID links this run to 65 a chair and the Run ID links this run to more extensive information about the run. Example:

16

Chair ID: 000000001 Run ID: 001000100 Run Name: The Wall Run Info Table

The Run Info Table provides a Unique Run ID, a Run Name and other information about the Runs. The Run ID links a run record to a specific run. Example:

Run ID: 001000100 Run Name: The Wall Level: Advanced Length: 5000' Vertical 1600 Facilities Table

The Facilities Table provides a Unique Resort ID, a Facility ID and a Facility Name. The Resort ID links a Facility to a resort, the Facility ID links the Facility to a Facility Record and the Name is the common name of the Facility. Example:

Resort ID: 000909190 Facility ID: 001000010 Facility Name: Ski Rental

When creating the Resort Facilities Screen, the number of 25 facilities associated with the resort may be looked up in this table to determine the screen layout.

Facility Info Table

The Facility Info Table provides a Unique Facility ID and further descriptive and informational items. The Facility ID 30 links this record to the Facilities Table. Example:

Facility ID: 001000010 Facility Name: Ski Rental

Hours: 7:30-5:30 Daily

The Facility Info table is used to label the Button Objects. to determine the button image, and to associate data with a button so that when a user activates the button, the correct action will be initiated such as filling a text window or running an appropriate video.

Activities Table

The Activities Table provides a Unique Resort ID, a Facility ID and an Activity Name. The Resort ID links an Activity to a specific resort, and the Activity ID links an

Resort ID: 000909190 Activity ID: 002000001 Activity Name: Swimming

When laying out the Resort Activities Screen, the number of activities associated with the resort is looked up to determine the screen layout.

Activities Info Table

The Activities Info Table provides a Unique Activity ID and other information about the Activity. The Activity ID 55 links an Activity to a record about that activity. Example:

Activity ID: 002000001 Activity Name: Swimming

Hours: 9-5 Daily Cost: \$10 per day

The Activity Info table is used to label the Button Objects, determine the button image and associate data with a button so that when a user activates the button, the correct action will be initiated such as filling a text window or running an appropriate video.

We turn now to a description of the individual tables making up the shops and manufacturers joined table of FIG.

5. This series of tables describes the equipment side of the kiosk system that links ski shops to ski equipment manufacturers and their products. The user interface for a kiosk in a ski shop may be created on the fly from the information in these tables. For example, for a kiosk in the ABC Ski Shop 5 the Shops table will be linked to the manufacturer table and the manufacturer products table (referred to as Shop Items). The joined table provides the content for the Shop. The screen for the ABC Ski Shop will be populated based on the information in the joined table by performing a lookup of the 10 Manufacturers and the type of associated information to create the interface. If the ABC Ski Shop carries skis from X Company, for example, then an X Company Ski Button will be placed on the screen. A significant point here is that the information about X Company skis is already in the 15 database. It is only necessary that a table entry be included to indicate that the ABC Ski Shop carries X Company skis. As before, the appropriate number of button objects are placed according to a predefined screen type or by mathematical algorithm specifying screen coordinates.

The individual tables comprising FIG. 4 will now be described.

Shop Table

The Shop Table provides a Unique Shop ID, a shop name and address. The Shop ID provides a link to the Shop Items 25 database. Example:

iShop: 0001

sShop: ABC Ski Shop

Based on the Shop ID a table lookup may be performed in the ShopsItem database. This will allow the system author to determine the items the shop carries. The Shop Table will generally also include address information and in particular may include a telephone or fax line, which can be used for downloading and uploading information with the kiosk.

Shop Items Table

The ShopItems table provides a Unique Item ID, a reference to the shop and a boolean value indicating whether the shop carries the item. If the shop carries the item, a table lookup can be performed in the Items table to obtain the attributes of the item or information about that item. Example:

iItem: 00001 iShop: 0001 fAvailable: True

Based on the iltem ID and the boolean value, information can be gathered about the shops inventory.

Items Table

The Items table contains all items from all manufacturers.
The table includes an iltem ID, which specifies what the item is, an ItemType, which specifies what the type is, and a Manufacture ID, which specifies what Manufacture makes that Item. Example:

iItem: 00001 iItemType: 00100 iManufacture: 10000 sltem: Skis

Male: Male or Female sSizeForm: Sizes

This table links all the items to the shop and manufacturers.

Item Type Table

The table contains an Item Type ID and a description. The Item Type ID links an item type to an item. Example:

iltemType: 00100 sItemType: Alpine Skis This table links an item to an item type. Manufacturer Table

The Manufacturer table contains information on all manufacturers. It includes a unique Manufacturer ID, address information and any other relevant information. Example:

iManufacture: 10000
sManufacture: X Company
sAddress: \_\_\_\_
sCity: \_\_\_\_
sState: \_\_\_
sCounty: \_\_\_
The Manufacturer II) links are

The Manufacturer II) links an item to the Manufacturer of that item.

The authoring system is implemented in the embodiment illustrated here by means of a C++ interface to access the fields of the database as defined in the above sample tables. Standard Btrieve calls are used to access database. Software code generally referred to as a wrapper is written around the Btrieve API for linking the C++ interface to the Betrieve calls. The generation of such code is routine given the benefit of the disclosure herein and need not be described in detail here. Nevertheless here is a sample of such code.

```
The following are all member variables from the CMADbase Class.
         Public data members:
         BTTWORD
         BTI_BYTE
                             m_keyBuf[255];
         BTI_SINT
                             m_status
         Private data memebrs:
                             posBlock[128];
         BII_BYTE
                             dataBut[255],
         BTI_BYTE
         BTI_WORD
                             dataLen;
         BTI_WORD
                             keyNum = 0;
         BTI SINT
                             status
         unsigned char m_fileOpen = FALSE;
         These are structures defined for the Btrieve Records
         struct
              FILE_SPECS fileSpecs:
              KEY_SPECS keySpecs[2];
         } fileCreateBuf;
    Member Functions
    Function Name: Open
    Description: Provide a wrapper for Btrieve Open File function
    BOOL CMADBase::Open(CString sFileName)
           strepy((BTI_CHAR*)m_keyBuf, sFileName);
           m kevNum = 0:
           m_datalen = sizeof(fileCreateBuf);
           m_status = BTRV(B_OPEN, m_posBlock, m_dataBuf,
               &m_datalen, m_keyBuf, m)keyNum);
           if (m_status = = B_NO_ERROR)
               m_fileOpen = TRUE:
              return TRUE;
               DisplayError(m_status);
55
               return FALSE:
    Functin Name: Close
    Description: Provide a wapper for the Btrieve Close File function
    BOOL CMADbase::Close()
         if (m_fileOpen)
               m_dataLen = 0;
               m_status = BTRV(B_CLOSE, m_posBlock, m_dataBuf,
                    &m_dataLen, m_keyBuf, m_keyNum);
               if (m_status = = B_NO_ERROR)
```

-continued

return TRUE;
}
else
{
 DisplayError(m\_status);
 return FALSE;
}
return FALSE;
}

Providing wrapper functions around the Btrieve code gives the flexibility to switch to a different database in the future. When a new database is introduced, it is only 15 necessary to change these wrapper functions. The code in the rest of program does not have to be altered.

The manner disclosed herein for defining a user interface for a specific kiosk has the advantage that to change the interface one need only perform a database lookup and fill 20 out definition files for each kiosk. When the ABC Ski Shop first decides to place a kiosk in the shop, an ABC kiosk definition table is filled out for the ABC Ski Shop and entered into the database. The kiosk interface screens may then be quickly defined from database lookups. At a later 25 time if the ABC Ski Shop should sell out of a model of X Company ski boots, that item can be removed from the definition table and the affected interface screen re-defined to remove any buttons or other objects that may have been associated with the sold-out item.

As mentioned above, when a central database server is not used, it is advantageous for each kiosk to contain the complete database, even including tables that will not be used at that kiosk. When the database tables are modified, for whatever reason, the modified database can be down- 35 loaded to each kiosk in the system. The advantages following from this are as follows. Version control: uncontrolled propagation of multiple version throughout the kiosks in the field is prevented. The need to keep track of which version each kiosk has is avoided. In this manner it is also easier to 40 keep comply with contractual obligations to keep each subscriber updated with the latest version. Kiosk portability: A kiosk unit may be moved from one subscriber to another with no change of software or reconfiguration other than providing a definition file. Control over changing informa- 45 tion providers: A ski shop may drop one line of product for a competitor's line. The ski shop's kiosk will already be configured for the full range of information providers. It is then only necessary to change a definition file. Loading and unloading of a multiplicity of information provider files is 50 avoided. Broadcasting: It is easier to broadcast messages, for example, when X Company runs out of or discontinues a particular ski, this change can be made once and broadcast to all subscribers. Local and remote configuration: The local layout for a particular kiosk subscriber can be configured 55 either at the subscriber's location or remotely. This would not be feasible if the full database were not available at the subscriber's kiosk.

The above descriptions and drawings disclose illustrative embodiments of the invention. Given the benefit of this 60 disclosure, those skilled in the art will appreciate that various modifications, alternate constructions, and equivalents may also be employed to achieve the advantages of the invention. For example, given the benefit of this disclosure, those skilled in the art will be able to implement kiosks in 65 other subject areas than skiing and skiing-related subjects, which is only offered as an example. Therefore, the inven-

tion is not to be limited to the above description and illustrations, but is defined by the appended claims.

What is claimed is:

- 1. In an electronic kiosk system having a plurality of interactive electronic kiosks for displaying information from a plurality of information providers, a method for presenting customized assortments of said information from said plurality of information providers at individual kiosks of said plurality, comprising:
  - providing access to information from said plurality of information providers for prospective display on said plurality of kiosks;
  - providing a plurality of pre-defined interface screen elements for prospective inclusion in a custom interface screen, wherein at least one of said screen elements permits limited variation in its on-screen characteristics in conformity with a desired uniform look and feel for said interface screens on the kiosks of said kiosk system,
    - wherein said plurality of pre-defined interface screen elements includes at least one element for displaying information and at least one activation site for use in obtaining information for display from at least one of said information providers;
  - enabling a kiosk user to select one or more screen elements from said pre-defined screen element plurality and to select on-screen characteristics of at least one screen element permitting limited variation in its on-screen characteristics;
  - enabling said kiosk user to select an assortment of information from at least a portion of said information providers to define kiosk information content for an individual kiosk of said system; and
  - associating said user selected kiosk information content with at least a portion of said selected screen elements, and associating said activation site with the displaying of at least a portion of said user selected kiosk information content.
  - 2. The method of claim 1 wherein said enabling a kiosk user to select screen elements and on-screen characteristics comprises presenting items available for selection to said kiosk user from the group of window sizes, window positions, background colors, and foreground colors.
  - 3. The method of claim 2 wherein the group from which said items for presentation to said user are selected further comprises background images and labels.
  - 4. The method of claim 1 wherein said activation site is selected from the group of buttons and hot spots.
  - 5. The method of claim 1 wherein said enabling a kiosk user to select screen elements and on-screen characteristics further comprises downloading an identification of said pre-defined screen elements and on-screen characteristics available for selection.
  - 6. The method of claim 5, wherein each of said screen elements permitting limited variation in their on-screen characteristics has associated therewith at least one variable attribute governing the on-screen characteristics thereof, and said enabling a kiosk user to select screen elements and on-screen characteristics further comprises:
    - enabling said kiosk user to select a value for each said variable attribute.
  - 7. The method of claim 1, further comprising downloading an identification of said information available for selection.
  - 8. The method of claim 1, wherein said kiosk system includes a system server in communication relation with

said kiosk and enabling the uploading of said user's selection of items to said system server.

- 9. The method of claim 8, wherein said uploading includes said user's selection of pre-defined screen elements and on-screen characteristics.
- 10. The method of claim 8, wherein said uploading comprises said user's selection of information.
- 11. The method of claim 1, further comprising downloading an indication of said user's selection of pre-defined screen elements and attribute settings to the kiosk of said user.
- 12. The method of claim 1, further comprising downloading an indication of said user's selection of information categories to the kiosk of said user.
- 13. The method of claim 1 wherein said plurality of pre-defined interface screen elements are provided over a global computer network and said user at an individual kiosk is enabled to select said screen elements and on-screen characteristics and said information over said global computer network.
- 14. In an interactive computer system including a plurality of computers for displaying information from a plurality of information providers, a method for presenting customized assortments of said information from said plurality of information providers at individual computers of said plurality, comprising:

providing access to information from said plurality of information providers for prospective display on said plurality of computers;

providing a plurality of pre-defined interface screen elements for prospective inclusion in a custom interface screen, wherein at least one of said screen elements permits limited variation in its on-screen characteristics in conformity with a desired uniform look and feel for said interface screens on the computers of said system, wherein said plurality of pre-defined interface screen elements includes at least one element for displaying information and at least one activation site for use in obtaining information for display from at least one of said information providers;

enabling a user at an individual computer of said plurality to select one or more screen elements from said predefined screen element plurality and to select on-screen characteristics of said at least one screen element permitting limited variation in its on-screen characteristics;

enabling said user to select an assortment of information from at least a portion of said information providers to define individual information content for an individual computer of said system; and

associating said user selected individual information content with at least a portion of said selected screen elements, and associating said at least one activation site with the displaying of at least a portion of said user —selected individual information content.

15. The method of claim 14 wherein said enabling a kiosk user to select screen elements and on-screen characteristics comprises presenting items available for selection to said user from the group of window size, window position, background color, and foreground color.

16. The method of claim 15 wherein the group from which said items for presentation to said user are selected further comprises background images and labels.

17. The method of claim 14 wherein said activation site is selected from the group of button and hot spot.

18. The method of claim 14 wherein said enabling a user at an individual computer to select screen elements and

on-screen characteristics further comprises downloading an identification of said pre-defined screen elements and on-screen characteristics available for selection.

19. The method of claim 18, wherein each of said screen elements permitting limited variation in their on-screen characteristics has associated therewith at least one variable attribute governing the on-screen characteristics thereof, and said enabling a user at an individual computer to select further comprises:

enabling said user to select a value for each said variable attribute.

- 20. The method of claim 14, further comprising down-loading an identification of said information categories available for selection.
- 21. The method of claim 14, wherein said computer system includes a system server in communication relation with said individual computers and enabling the uploading of said user's selection of items to said system server.
- 22. The method of claim 21, wherein said uploading includes said user's selection of pre-defined screen elements and on-screen characteristics.
- 23. The method of claim 21, wherein said uploading comprises said user's selection of information.
- 24. The method of claim 14, further comprising downloading an indication of said user's selection of pre-defined screen elements and attribute settings to the computer of said user.
  - 25. The method of claim 14, further comprising downloading an indication of said user's selection of information to the computer of said user.
  - 26. The method of claim 14 wherein said plurality of pre-defined interface screen elements are provided over a global computer network and said user at an individual computer is enabled to select said screen elements and on-screen characteristics and said information categories over said global computer network.
  - 27. In an electronic kiosk system having a plurality of interactive electronic kiosks for displaying information provided by a plurality of information providers, a method for defining custom interface screens customized for individual kiosks of said plurality and operable to make different assortments of said information available for display at different kiosks of said plurality, said method comprising:

providing a master database of information from said plurality of information providers, said master database referencing information content from said providers to be displayed on any of said plurality of kiosks;

providing a plurality of pre-defined interface screen element types, each element type defining a form of element available for presentation on said custom interface screens, wherein each said element type permits limited variation in its on-screen characteristics in conformity with a desired uniform look and feel for said interface screens on all kiosks of said kiosk system,

each element type having a plurality of attributes associated therewith, wherein each said element type and its associated attributes are subject to pre-defined constraints providing element characteristics in conformance with said uniform look and feel for said interface screens, and

wherein said plurality of pre-defined element types includes at least one pre-defined window type, at least one pre-defined hot spot type, and at least one pre-defined multimedia type;

selecting a plurality of elements to be included in a custom interface screen under construction, said plu-

rality of elements being selected from said plurality of pre-defined elements types, said plurality of selected elements including at least one hot spot type;

assigning values to the attributes associated with each of said selected elements consistent with said pre-defined constraints, whereby the aggregate layout of said plurality of selected elements on said interface screen under construction will have a uniform look and feel and be functionally operable for effective delivery of information to a kiosk user;

selecting from said master database an assortment of information content deriving from selected ones of said information providers to define kiosk information content for an individual kiosk of said kiosk system;

associating said kiosk information content with at least a portion of said selected elements for said interface screen under construction; and

linking said at least one selected hot spot type element to an action facilitating the viewing of at least portions of said kiosk information content by a kiosk user.

28. The method of claim 27 wherein said selecting an assortment of information content from said master database comprises:

maintaining a kiosk definition table for each kiosk of said 25 kiosk system identifying the information content of said master database to be associated with the respective kiosk.

29. The method of claim 28, further comprising populating an individual kiosk definition table with the respective 30 kiosk information content by querying said master database.

30. A method of customizing interface screens for presentation by individual computers of a plurality of computers coupled by a network for receiving information provided by a plurality of information providers, the interface screens being customized to enable computer users to interactively access, in customized screen types, different assortments of information from the information providers at different computers of the plurality of computers, the method comprising:

with changing screen.

34. The method values comprises:

assigning a locate designate control type.

35. The method values comprises:

providing a master database of information from the plurality of information providers, the master database storing information content from the plurality of information providers to be displayed on any of the plurality of computers;

providing a plurality of pre-defined interface screen types, each pre-defined interface screen type defining a form of screen available for presentation on the interface screens being customized and permitting limited variation in at least one on-screen characteristic of the pre-defined interface screen type in conformity with a desired uniform look and feel for the interface screens on the computers,

each pre-defined interface screen type having a plurality of attributes associated therewith, wherein each plurality of attributes are subject to pre-defined constraints providing the on-screen characteristics in conformance with the uniform look and feel for the interface screens, and

38. The method values comprises:
assigning a value of a location defined control of the pre-de with the objection of the pre-de with the obje

wherein each of the plurality of pre-defined interface screen types references at least one pre-defined control type providing for user interaction via the interface screens being customized; selecting at least one pre-defined interface screen type for the interface screen being customized, the predefined interface screen type being selected from the plurality of pre-defined interface screen types;

assigning values to the attributes associated with the at least one selected pre-defined interface screen type, the values being consistent with the pre-defined constraints, whereby the interface screen being customized will have a uniform look and feel and be functionally operable for delivery of information to a computer user;

selecting from the master database an assortment of information content deriving from selected ones of the information providers to define a customized selection of information content for the interface screen being customized; and

associating at least portions of the customized selection of information content with the interface screen being customized.

31. The method of claim 30 wherein the pre-defined control type referenced by the pre-defined interface screen type is selected from a hot spot linked to an action, a pre-defined window type, a pre-defined button type, and a pre-defined multimedia type.

32. The method of claim 30 wherein the pre-defined interface screen type references at least one pre-defined window type, at least one pre-defined button type, and at least one pre-defined multimedia type.

33. The method of claim 30 further comprising:

linking the pre-defined control type referenced by the pre-defined interface screen type to an action associated with changing the appearance of the custom interface screen.

34. The method of claim 30 wherein the assigning of values comprises:

assigning a location value to at least one of the attributes to designate a location of an object of the pre-defined control type.

35. The method of claim 30 wherein the assigning of 40 values comprises:

assigning a color value to at least one of the attributes to designate a color associated with an object of the pre-defined control type.

36. The method of claim 30 wherein the assigning of 45 values comprises:

assigning a font value to at least one of the attributes to designate a font associated with an object of the predefined control type.

37. The method of claim 33 wherein the assigning of 50 values comprises:

assigning a color value to at least one of the attributes to designate a color associated with an object of the pre-defined interface screen type.

38. The method of claim 30 wherein the assigning of values comprises:

assigning a value to the attributes to designate at least one of a location associated with an object of the predefined control type, a color associated with the object of the pre-defined control type, a font value associated with the object of the pre-defined control type, and a color associated with an object of the pre-defined interface screen type.

\* \* \* \* :